ORACLE LIGHTING
By Elite Lighting

EASY 3 COLORS SELECCTOR
3500K • 4000K • 5000K

OWP-FC-226-LED
LED Wallpack Light



DIMENSIONS



Net Weight:

70W: 9.2164lb 100W: 9.4148lb

BACK BOX DIMENSIONS (SOLD SEPERATELY)



FEATURES

Cast in a modern and low-profile design, OWP-FC-226-LED series is easily customized to fit every building's design aesthetic and a mix of architectural styling and energy savings. Available in two sizes, the OWP-FC-226-LED family delivers 3000 to 6,000 lumens with a wide, uniform distribution. It's ideal for illuminating commercial office buildings, warehouses, campuses, shopping malls and other office complexes.

LUMENS	3000L/4000L/5000L/6000L
CCT	30K/40K/50K
CRI	80+ Standard
COLOR QUALITY	3 Step MacAdam Ellipse
MOUNTING	Surface Mount
DIMMING	Dim10 (0-10 dimming)
DISTRIBUTION	Type III
FINISH	Dark Bronze, White, Black
WORKING TEMPERATURE	-40°C to 40°C (-40°F - + 104°F)
SURGE PROTECTION	6kV
LIFETIME	L70 at 50,000 Hours
PHOTOMETRIC TESTS	In Accordance with IES LM79-08, LM80 and TM-21
EMERGENCY	O-EMG-8W

NOMINAL LUMENS	DELIVERED LUMENS	WATTAGE
3000	2900	34W
4000	3900	43W
5000	4905	55W
6000	6080	66W

Based on 4000K, 85+ CRI. Actual wattage may vary +/- 5%

BUG RATING

B	U	G
2	0	2

Due to the changes of constant improvement in LED technology, all details are subject to change without notice. Consult factory for up to date information.
MMDDYY

ORACLE LIGHTING
By Elite Lighting

OWP-FC-226-LED
LED Wallpack Light

OPTICS
• Scalable Lumen Packages from 6,000 to 14,000 Lumens.
• Zero uplight distributions using individual acrylic.
• High performance UV stabilized optical grade polymer refractor lenses to achieve desired distribution optimized to get maximum spacing, target lumens and a superior lighting uniformity.

CONSTRUCTION
• Sealed die-casting profile for outdoor applications.
• Casting thermally conducts LED heat to optimize performance and long life.
• Suitable for applications requiring 3G testing prescribed by ANSI C136.31.

OPTIONS & ACCESSORIES
Options and Accessories

Optional emergency battery back-up (EMG) option for emergency egress lighting

Optional photocell (PHC) detects changing light levels and saves energy by turning off during the day

DRIVER ELECTRICAL INFORMATION
• Universal 120-277 VAC input voltage.
• DIM10 (1-10V Dimming)
• Both drivers have a power factor >90%, THD <20%.
• Operating Temperature Range: -40°C to 40°C (-40˚F - + 104˚F).

WARRANTY
Five-year warranty for parts and components (labor not included).

LISTING
c-UL-us Listed for Feed Through Wiring.
Listed for DLC, California Title 24 compliant.

ISO FOOTCANDLE

MOUTNING HEIGHT= 10FT

Red Line= 0.1fc
Orange Line= 0.5fc
Blue Line= 1fc



OCCUPANCY HEIGHT

Sensor height up to 40ft



Plug in Sensor

MOUNTING

The Surface-Mounted Back Box, while optional, offers versatile installation options. It not only facilitates standard J-box installation but also accommodates outer-surface conduit wiring through the 1/2" knockouts on all four sides, eliminating the need for a J-box.

Example: **OWP-FC-226-LED-3000L/4000L/5000L/6000L-DIM10-MVOLT-30K/40K/50K-BK**

OWP-FC-226-LED						
SERIES	LUMENS	DIMMING	VOLTAGE	CCT	FINISH	OPTION
OWP-FC-226-LED Wall Mount Wall Pack	**3000L/4000L/5000L/6000L**	**DIM10 - 0-10V Dimming**	**MVOLT**	**30K/40K/50K**	**WH** - White **BK** - Black **BZ** -Bronze	**PHC** - Photocell **O-EMG-LED-5W-HV** - Emergency **MS** -Motion Sensor **PIR** - PIR Sensor **BB**- Back Box

Due to the changes of constant improvement in LED technology, all details are subject to change without notice. Consult factory for up to date information.